

UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2026-27/

Date: 01.07.2026.

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **03.07.2026 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 03.07.2026 at 12.00 PM

Opening of Quotations: 03.07.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	Providing & fixing of 36w false ceiling fitting and wiring in C-250 lab at medical Sciences building in U.O.H campus Reg.	Rs. 49,500/-

Sd/-
Assistant Engineer (E)

Name of Work:-Providing & fixing of 36w false ceiling fitting and wiring in C-250 lab at School of Medical sciences building in U.O.H						
1) The estimate amount is inclusive of GST.						
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.						
SCHEDULE OF QUANTITIES						
S. No	DSR	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1		Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS/HFFR PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.				
1.1	1.14.3	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	10	mtrs	Figure:Rs_____ Words:Rupees_____	
2	MR	Supply, installation, testing & commissioning of 36Watt 2X2 ft LED false ceiling fittings etc as required. Make:- Crompton/Philips.	17	Each	Figure:Rs_____ Words:Rupees_____	
3	MR	Removing, Re-Installation of ceiling fan with providing of 3 feet down rod length including wiring the down rods (upto 1.1 mtr) with 1.5 sq. mm FRLS PVC insulated copper conductor, single core cable from ceiling rose etc. as required.	8	Each	Figure:Rs_____ Words:Rupees_____	
4	1.17	Supplying and drawing following sizes of FRLS/HFFR PVC insulated Copper conductor,single core cable in the existing surface/recessed steel/PVC conduit as required.				
4.1	1.17.2	2*1.5 sq.mm	50	mtrs	Figure:Rs_____ Words:Rupees_____	
Sub Total						
Add GST @ 18%						
Total						
1) The estimate amount is inclusive of GST.						
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.						
Signature of the Contractor			SD/ Assistant engineer			

Terms & Conditions:

- The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central
- The work should be completed within Seven (7) days from the date of issue of work order. Failure to complete the work within the
- The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
- This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
- The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for
- The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
- If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
- Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
- Defect liability period 6 (six) months from the date of completion of the work.
- For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
- A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.
- No quotation will be accepted without PAN/VAT no.
- TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

**SD/
Assistant Engineer**

CC to:

- A.E. Sub-Division (E)
- S O (Works & Bills),
- O.C.,
- D.B.,