

UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2025-26/

Date: 17.07.2026

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **21.07.2026 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details:-

Submission of Quotations by 21.07.2026 at 12.00 PM

Opening of Quotations: 21.07.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	Replacement of 3.5 core x 25sqmm UG cable from LT panel to DB at J & K Hostel Dining Hall, in University of Hyderabad Campus.	RS. 46,781/-

Assistant Engineer (E)

Name of Work: - Replacement of 3.5 core x 25sqmm UG cable from LT panel to DB at J & K Hostel Dining Hall, in University of Hyderabad Campus .

1) The estimate amount is inclusive of GST.

2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.

SCHEDULE OF QUANTITIES

S. No	D.S.R./ MR	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	11.1	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
1.1	11.1.20	3½ X 25 sq. mm (28mm)	4	Set	Rs_____ Words:Rupees_____	
2	MR	Supply of 3.5 core x 25 sqmm XLPE insulated Aluminium Armoured cable of 1.1 KV grade etc as required. Make: Finolex/Polycab/Havells.	80	Meter	Rs_____ Words:Rupees_____	
3	MR	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of 25Sqmm size in 50mm Outer dia DWC HDPE pipe (white colour) ISI marked along with all accessories like socket, bend, couplers etc. conforming to IS 14930, Part II complete with fitting and jointing etc along with accessories on wall surface (clamped with 1mm thick saddle) as required.	80	mtrs	Rs_____ Words:Rupees_____	
4	Civil DSR 2023 18.76	Cutting holes up to 30x30 cm in walls including making good the same:				
4.1	18.76.1	With common burnt clay F.P.S. (non modular) bricks.	3	Each	Rs_____ Words:Rupees_____	
		Sub Total				
		GST @ 18%				
		Total				

Signature of the Contractor

Assistant Engineer

Terms & Conditions:

1. The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central
2. The work should be completed within Fifteen (15) days from the date of issue of work order. Failure to complete the work within the stipulated
3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for
6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
9. Defect liability period 6 (six) months from the date of completion of the work.
10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.
12. No quotation will be accepted without PAN/VAT no.
13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Assistant Engineer