

**UNIVERSITY OF HYDERABAD**  
**ENGINEERING DEPARTMENT**

Office of the Assistant Engineer

---

**NOTE**

Ref: UH/ENGG/UE/2025-26/

Date: 17.07.2026

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **21.07.2026 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details:-

**Submission of Quotations by 21.07.2026 at 12.00 PM**

**Opening of Quotations: 21.07.2026 at 3.00 PM**

| S. No | Name of the work                                                                                                | Estimated Cost Rs.  |
|-------|-----------------------------------------------------------------------------------------------------------------|---------------------|
| 1     | Replacement of 3.5 core x 25sqmm UG cable from LT panel to DB at A & H Mess, in University of Hyderabad Campus. | <b>RS. 44,611/-</b> |

**Assistant Engineer (E)**

**Name of Work: -Replacement of 3.5 core x 25sqmm UG cable from LT panel to DB at A & H Mess, in University of Hyderabad Campus .**

**1) The estimate amount is inclusive of GST.**

**2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**

**SCHEDULE OF QUANTITIES**

| S. No | D.S.R./<br>MR | Description of item                                                                                                                                                                                                                                                                         | Qty | Unit  | Rate in figures & Rate in words | Amount |
|-------|---------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|-------|---------------------------------|--------|
| 1     | MR            | Supply and laying of 3.5 corex 25 Sqmm XLPE Aluminium Armoured power cable of 1.1 KV grade direct in ground (75 cm below ground level) including excavation, protective covering and refilling the trench etc as required, but excluding sand cushioning.<br>Make: Finolex/Polycab/Havells. | 55  | Meter | Rs_____                         |        |
|       |               |                                                                                                                                                                                                                                                                                             |     |       | Words:Rupees_____               |        |
| 2     | MR            | Supply and laying of 3.5 corex 25 Sqmm XLPE Aluminium Armoured power cable of 1.1 KV on wall surface as required. etc as required.<br>Make: Finolex/Polycab/Havells.                                                                                                                        | 10  | Meter | Rs_____                         |        |
|       |               |                                                                                                                                                                                                                                                                                             |     |       | Words:Rupees_____               |        |
| 3     | 10.10         | Supplying and fixing cable route marker with 10 cm X 10 cm X 5 mm thick G.I. plate with inscription there on, bolted /welded to 35 mm X 35 mm X 6 mm angle iron, 60 cm long and fixing the same in ground as required.                                                                      | 5   | Each  | Rs_____                         |        |
|       |               |                                                                                                                                                                                                                                                                                             |     |       | Words:Rupees_____               |        |
| 4     | 11.1          | Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.                                                                                     |     |       |                                 |        |
| 4.1   | 11.1.20       | 3½ X 25 sq. mm (28mm)                                                                                                                                                                                                                                                                       | 2   | Each  | Rs_____                         |        |
|       |               |                                                                                                                                                                                                                                                                                             |     |       | Words:Rupees_____               |        |
| 5     | MR            | Cutting holes up to required size in walls to lay cable through wall etc as required.                                                                                                                                                                                                       | 4   | Each  | Rs_____                         |        |
|       |               |                                                                                                                                                                                                                                                                                             |     |       | Words:Rupees_____               |        |
|       |               | <b>Sub Total</b>                                                                                                                                                                                                                                                                            |     |       |                                 |        |
|       |               | <b>GST @ 18%</b>                                                                                                                                                                                                                                                                            |     |       |                                 |        |
|       |               | <b>Total</b>                                                                                                                                                                                                                                                                                |     |       |                                 |        |

**Signature of the Contractor**

**Assistant Engineer**

**Terms & Conditions:**

1. The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central
2. The work should be completed within Fifteen (15) days from the date of issue of work order. Failure to complete the work within the stipulated
3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for
6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
9. Defect liability period 6 (six) months from the date of completion of the work.
10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.
12. No quotation will be accepted without PAN/VAT no.
13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

**Assistant Engineer**